

To: 1120790
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S-3

API NUMBER 15-185-20,302-0000

SW SE SW, SEC. 19, T 23 S, R 12 W/X
330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023
Operator: Kansas Petroleum, Inc.
Name & Address 225 N. Market, Ste. 310
Wichita, KS 67202

Lease Name Meyer Well # 1
County Stafford 126.91
Well Total Depth 3905 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 845, Pratt, KS 67124

Company to plug at: Hour: 11:30 a.m. Day: 3 Month: 5 Year: 19 93

Plugging proposal received from Bill Euck

(company name) Kansas Petroleum, Inc. (phone) 316-792-2051

Work: 4 1/2" at 3901' w/225 sx cement, PBTB 3848', Perfs at 3601-07, 3563-68, 3458-60'
1st plug sand back to 3405' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 p.m. Day: 3 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3405' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION

MAY 14 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXX / did not) observe this plugging.

DATE 5-17-93

WV. NO. 37718

Signed Duane Rankin
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas