

1070031

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-185-20,656-0000  
150' NE of  
SW SE SW, SEC. 21, T. 23 S, R. 12 W/E  
405 feet from S section line  
3555 feet from E section line

7-18

TECHNICIAN'S PLUGGING REPORT

Operator License # 6981

Lease Name Bayne Well # 1

Operator: Gas Marketing, Inc.

County Stafford 124.89

Name & Address P.O. Box 159

Well Total Depth 3843 feet

Stafford, KS 67578

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:45 a.m. Day: 18 Month: 7 Year: 19 96

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

logs: 5 1/2" at 3842' w/150 sx cement, Open hole 3842-43'

1st plug sand back to 50' above open hole and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:15 a.m. Day: 18 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3790' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement; 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in 500 psi.

RECEIVED  
KANSAS CORPORATION COMMISSION  
7-23-96  
JUL 23 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1700' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED  
I (date) 7/25/96 observe this plugging.

DATE JUL 25 1996

Signed [Signature] (TECHNICIAN)

INV. NO. 46092