

1 090388

15-055-00053-0000

Comp. 4-12-60

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE SW, SEC. 16, T. 21 S, R. 33 W XX

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Hyer "A" Well # 1

Operator: Cities Service Oil & Gas Corp.
Name & Address: 3545 NW 58th Street
Oklahoma City, OK 73112

County Finney 153.24

Well Total Depth 4715 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Daco, Inc. License Number 6416

Address Drawer 3010, Borger, TX 79007

Company to plug at: Hour: 8:00 am Day: 7 Month: December Year: 19 85

Plugging proposal received from Steve Milinichik

(company name) Cities Service (phone) 405-949-4400

were: 5 1/2" at 4714' PBD 4250' Perfs at 4185-4188' Anhydrite at 1950'

Pump through 5 1/2" casing with mud between plugs

1st plug set CIBP at 4000' with 2 sx cement

2nd plug at 1950' with 50 sx cement

If the plug at 1950' is not possible, set 80 sx at the top of the Glorietta

3rd plug at 250' with 50 sx cement

solid bridge - hulls -- plug at 40' -- cement to surface with

4th plug 10 sx cement Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 pm Day: 9 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4000' with 2 sx cement on top, 2nd plug

at 1018' with 80 sx cement, 3rd plug at 250' with 50 sx cement, 4th & 5th plugs -

solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Richard Lacey seen part of the plugging on 12/7/85

Remarks: Recovered 1019' 5 1/2" casing. Used common cement by Daco
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 18 1985

INV. NO. 11592

STATE CORPORATION COMMISSION

Signed R. B. Tarbutton (TECHNICIAN)

DEC 16 1985 12-16-85