

1 050986

1-13-88 15-055-00181-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 4/14/61
C SE., SEC. 15, T. 21 S, R 33 W/E
8 1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Hobbs Well # 1

Operator: A.L. Abercrombie, Inc.

County Finney 86.35

Name & Address 801 Union Center Bldg.

Well Total Depth 2657.5 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 7 1/2 feet 350

Abandoned Oil Well _____ Gas Well x Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 13 Month: 1 Year: 19 88

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 2657' Perfs at 2595-2620, 2591-95' Elevation 2903' KB

1st plug pump 1 sx hulls and 20 sx common cement.

2nd plug pump 400 lbs. hulls, 5 sx gel, 60 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 13 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx common cement, plug stopped at 1342

2nd plug pumped 4 sx hulls, 5 sx gel, 60 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
01-15-88

JAN 15 1988

Maximum pressure 800 psi and shut in 100 psi.

Remarks: Used common and 60/40 Pozmix 6% gel by Allied. Recovered 1300' casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, observe this plugging.)

Signed Richard W. Lacey
(TECHNICIAN)

DATE 1-15-88

INV. NO. 19582