



15-185-30039-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 31 1965
CONSERVATION DIVISION
Wichita, Kansas

3-31-65

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Boman of Tom-Kat Drilling Inc. has this date requested permission to plug the following described well:

Mr. Boman guarantees payment of the plugging fee.

Operator's full Name: Tom-Kat Inc.

Complete Address: 1125 Wichita Plaza, Wichita, Kansas

Lease Name: McBride Well No. # 1

Location: SE SE NE Sec. 14 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3818' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Boman was instructed to plug the well as follows:

275' of 8 5/8" surface pipe, cement circulated with 230 sacks.

Fill hole with drilling mud to 260', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving

Conservation Division Agent