



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-185-30220-0000

RECEIVED  
STATE CORPORATION COMMISSION

DEC 13 1965

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Otto Berens of Rex & Morris Drilling has this date requested permission to plug the following described well:

Mr. Berens guarantees payment of the plugging fee.

Operator's full Name: Rex & Morris

Complete Address: P. O. Box 334, El Dorado, Kansas

Lease Name: Riley Well No. # 1

Location: SW NE NE Sec. 29 Twp. 23 Rge. 12 (E) (W) W

County Stafford Total Depth 3855' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Berens was instructed to plug the well as follows:

246' of 8 5/8" surface pipe, cement circulated with 250 sacks.  
Fill hole with drilling mud to 225', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent