

9

State of Kansas



15-079-30069-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1967  
5 24-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bradley of Donald C. Slawson has this date requested permission to plug the following described well:

Mr. Bradley guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg. Wichita, Kansas

Lease Name: Krehbäel Well No. A-1

Location: C NW SW Sec. 7 Twp. 22 Rge. 2 (E/W)

County Harvey Total Depth 3295' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Bradley was instructed to plug the well as follows:

8 5/8"-204'-Circulated w/cement. 4 1/2"-3294'-Cemented. Top Perf. 3140'.

Packer left in hole, set at 3096'. Sand hole to 3050'.

4 Sax.cement 3050' to 3000'. Mud 3000' to 220'.

Bridge 220' to 210'. 25 Sax.cement 210' to 135'.

Mud 135' to 40'. Bridge 40' to 30'. 10 Sax.cement 30' to 0.

Pulled 2800'-4 1/2"-pipe.

Very truly yours,

Conservation Division Agent