



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 CORPORATION COMMISSION
 DEC 23 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

12-23-68

December 19, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Herren of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Herren guarantees payment of the plugging fee.

Operator's full Name: Donald T. Ingling

Complete Address: 615 First Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name: Willow Lake Well No. 1

Location: C SW NW NW Sec. 36 Twp. 22 Rge. 3 (E)(W) X


County: Harvey Total Depth 3795' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Herren was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/4 sack hulls to 250' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to 40'.
Push plug and 1/2 sack hulls pushed to 40' and hole cemented to base of
cellar with 10 sacks cement. Rathole ^{to be} bridged and cemented with 2 sacks
cement.

Very truly yours,



 Conservation Division Agent