

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-083-10269-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Co.

Complete Address: 321 W. Douglas, Wichita, Kansas

Lease Name: Dan Eway Well No. # 4

Location: C SE NW Sec. 17 Twp. 22 Rge. 22 (E) (W) W

County Hodgeman Total Depth 4537 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Deacon was instructed to plug the well as follows:

249' of 8 5/8" surface pipe, cement circulated with 225
sacks. 4511' of 5 1/2" long string, cemented with 125 sacks.
Plugged back to 4524'. Top perforation 4130'. Sand to 4120',
cement with 5 sacks. Fill hole with mud to 240', 10' rock
bridge, cement with 20 sacks. Fill hole with mud to 40', 10'
rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Audie Elving
Conservation Division Agent