



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 9 1963
 10-9-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Hall of Rains-Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Rains-Williamson Oil Co.

Complete Address: 412 Union Center. Wichita, Kansas

Lease Name: Ewy Well No. B-3

Location: SW NE Sec. 17 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4532' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

8 5/8"-257' Circulated w/cement. 4 1/2"-4530' Cemented.
Plug bottom w/sand 4532' to 4520' 5 Sax.cement 4520' to 4470'
Mid 4470' to 700' 25 Sax.cement 700' to 625'
Mid 625' to 250' 25 Sax.cement 250' to 175'
Mid 175' to 50' 10' Rock bridge 50' to 40'
15 Sax.cement 40' to surface. Weld cap on surface.

Very truly yours,

Hugh Scott
 Conservation Division Agent