



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Powell of Braden-Deem has this date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem

Complete Address: 200 East 1st., Wichita, Kansas

Lease Name: Ewy "B" Well No. 2

Location: SE NE Sec. 17 Twp. 22 Rge. 22 ^{XX} (E) (W)

County: Hodgeman Total Depth 4518' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Powell was instructed to plug the well as follows:

8 5/8" to 283' circulated w/ cement. 5 1/2" to 4511' cemented.

7' of open hole. Plug bottom w/ sand & 5 sacks cement.


Top of cement 4450' Mud 4450' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 250'

Spot 30 sacks cement 250' to 150' Mud 150' to 40'

Plug, & 10 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent