



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212-N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 30 1963

CONSERVATION DIVISION
 Wichita, Kansas

9-30-63

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Waston of Schultz, Turner & Webb has this date requested permission to plug the following described well:

Mr. Waston guarantees payment of the plugging fee.

Operator's full Name: Schultz, Turner & Webb

Complete Address: 1940 Mercantile Dallas Bldg, Dallas, Texas

Lease Name: Ewy Well No. B-1

Location: C NW NE Sec. 17 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4554 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Waston was instructed to plug the well as follows:

8 5/8"-335' Circulated w/250 Sax.cement. 5 1/2"-4533' Cemented w/100 Sax.

5 Sax.cement 4554' to 4520' Mud 4520' to 700'

25 Sax.cement spotted 700' to 575' Mud 575' to 325'

25 Sax.cement spotted 325' to 250' Mud 250' to 50'

Rock bridge 50' to 40' 15 Sax.cement 40' to surface.

Very truly yours,

Hugh Scott
 Conservation Division Agent