



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1964
03-09-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Holmstrom of Kansas Nebraska Natural Gas Co., Inc.

date requested permission to plug the following described well:

Mr. Holmstrom guarantees payment of the plugging fee.

Operator's full Name: Kansas Nebraska Natural Gas Co., Inc.

Complete Address: Box 608 Hasting, Nebraska

Lease Name: Wilson Well No. B 1

Location: C NE Sec. 33 Twp. 21 Rge. (E) (W) 33

County Finney Total Depth 2652' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Holmstrom was instructed to plug the well as follows:

8 5/8"-302' Circulated w/cement. 5 1/2"-2652' Cemented.

Plug back to 2636' Perforations 2609' Plug bottom 2636' to 2430'
W/rock & 20 Sax.cement.

Mud 2430' to 700' 25 Sax.cement 700' to 625'

Mud 625' to 300' 25 Sax.cement 300' to 225'

Mud 225' to 40' Plug, Hulls, 15 Sax.cement 40' to 0

Very truly yours,

[Signature]
Conservation Division Agent