

State of Kansas



15-055-00033-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

JAN 3 1968

01-03-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Gee of Eureka Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Gee guarantees payment of the plugging fee.

Operator's full Name: Eureka Drilling Company

Complete Address: Hamilton, Kansas

Lease Name: Wampler "A" Well No. 1

Location: C SE SE Sec. 17 Twp. 21 Rge. 33 ~~XX~~ (W)

County Finney Total Depth 4695' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gee was instructed to plug the well as follows:

8 5/8" to 240' circulated w/ cement. 5 1/2" to 4692' cemented.

Top perforations 4189' Plug bottom w/ 30 sacks cement.q

Top of cement 3800' Mud 3800' to 600'

Spotted 40 sacks cement 600' to 470' Mud 470' to 240'

Spotted 25 sacks cement 240' to 140' Mud 140' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

Conservation Division Agent