



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Daughty of Cities Service has this
date requested permission to plug the following described well:

Mr. Daughty guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1098, Liberal, Kansas

Lease Name: ~~Wampler~~ Wampler "A" Well No. 2

Location: C NE SE Sec. 17 Twp. 21 Rge. 33 (E) (W)

County: Finney Total Depth 4700' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Daugherty was instructed to plug the well as follows:

8 5/8" to 264' circulated w/ cement. 4 1/2" to 2716' cemented.

Top perforations 2519' Plug bottom w/ 20 sacks cement.

Top of cement 2355' Mud 2355' to 750'

Spot 25 sacks cement 750' to 650' Mud 650' to 260'

Spot 25 sacks cement 260' to 160' Mud 160' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent