



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1973
CONSERVATION DIVISION
Wichita, Kansas
02-07-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kelso of Thunderbird has this

date requested permission to plug the following described well:

Mr. ~~XXXX~~ Kelso guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Company

Complete Address: Box 18407, Wichita, Kansas

Lease Name: Wampler "A" Well No. 1

Location: NE NW Sec. 8 Twp. 21 Rge. 33 ~~(E)~~ (W)

County: Finney Total Depth 4710' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

8 5/8" to 419' circulated w/ cement. 5 1/2" to 4698' cemented.

Top perforations 4668' Plug bottom w/ sand & 5 sacks cement.

Top of cement. 4580' Mud 4580' to 400'

Spot 35 sacks cement 400' to 300' Mud 300' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent