

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 1 1963

CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Wayne Dobbs of Vaughan Drilling Inc. has this date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: Phillips and Vaughn Drilling Inc.

Complete Address: Box 825, Great Bend, Kansas

Lease Name: McCune Well No. # 1

Location: SE NW NE Sec. 35 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3695 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

241' of 8 5/8" surface pipe cemented with 210 sacks.  
Fill hole with mud to 180', 1st cementing plug, 1/2 sack  
hulls, cement with 20 sacks. Fill hole with mud to 40',  
2nd cementing plug, 1/2 sack hulls, cement with 10 sacks  
to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent