

STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 10-13-62

API No. 15-083-10287-0000

LEASE NAME Ray Lee 1

SPOT LOG (S.W. SE)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
660 Ft. from S Section Line
1980 Ft. from E Section Line

LEASE OPERATOR Berexco, Inc.
ADDRESS Box 723 Hays, Kansas 67601 m
PHONE (785) 628 6101 OPERATORS LICENSE NO. 5363

SEC. 16 TWP. 22 SRGE. 22 W (E) or (W)
COUNTY Hodgeman
Date Well Completed 10-13-62
Plugging Commenced 2/22/2000
Plugging Completed 2/25/2000

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/25/2000 (date)
by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4451
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD


Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	261	9 5/8		
	Casing	0	444	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Perf. at 600' 2 shots Trip in with WS to 4400' Pump 50 sk. common with 100 # hulls. Pull tubing to 1600'. Pump 25 sk. common. Pull tubing to 600' / Circulate cement to surface with 70 sk. 60/40 6% gel. TOH with tubing. Hook to casing and mix 70 sk. 60/40 6% gel stage to 300#. Hook to annulus Mix 70 sk. 60/40 6%. Shut in at 400#

Name of Plugging Contractor Berexco, Inc. License No. 5363
Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.
STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Mark Leiker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.



(Signature) Mark Leiker
(Address) Box 723 Hays, Mo. 67601

RECEIVED SUBSCRIBED AND SWORN TO before me this 2 day of March, 19 2000
STATE CORPORATION COMMISSION

Notary Public
5/10/2003

MAR 6 - 2000
My Commission Expires:

CONSERVATION DIVISION
Wichita, Kansas

Form CP-1
Revised 05-88