


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Hodgman County, Sec. 9 Twp. 22 Rge. 23 (E) (W)
Location as "NE/CNW/SW" or footage from lines C W/2 NE SW
Lease Owner Drillers Production Company
Lease Name Campbell #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4/20/72 19
Plugging completed 4/25/72 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eves
Producing formation Depth to top Bottom Total Depth of Well 4631 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	305	none
				5 1/2"	4619	2624'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, ran sand to 4600' and dumped 5 sacks of cement. Dug cellar, rigged up over 5 1/2" casing. Loaded hole, shot pipe at 3910', 3817', 3627', 3404', 3208', 3019', 2920', 2821', 2722', 2624', pipe came loose, pulled 81 joints of 5 1/2" casing. Allied pumped well with 5 sacks mud, 80 sacks cement, 4 sacks mud, 30 sacks cement, 3 sacks mud and 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 - 1972

CONSERVATION DIVISION
Wichita, Kansas

5-5-72

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of May, 1972

My commission expires



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Notary Public.

DRILLERS LOGCAMPBELL "B" NO. 1

CASING RECORD:	OPERATOR: Drillers Production Co.	DESCRIPTION:
8-5/8" @ 313'	CONTRACTOR: Sage Drilling Co., Inc.	C W/2 NE SW
w/225 sax cement	COMMENCED: March 23, 1971	Sec. 9-22S-23W
TOTAL DEPTH:	COMPLETED: April 1, 1971	Hodgeman County,
4619'		Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	309	
Shale	309	992	
Shale & Shells	992	1010	
Dakota Sand	1010	1285	
Shale	1285	1609	
Anhydrite	1609	1641	
Shale	1641	1700	
Lime & Shale	1700	2030	
Shale & Lime	2030	2401	
Lime & Shale	2401	4040	
Lime	4040	4073	
Lime & Shale	4073	4205	
Lime	4205	4619	5 1/2" @ 4619' w/100 sax cement

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1972
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 2nd day of April, 1971.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires November 26, 1974.