

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

Operator License No. 5447

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 26 TWP. 22S RGE. 22 E/~~W~~
Location as in quarters or footage from lines:
1980' FNL - 1980' FWL

Locate Well
correctly on above
Section Platt.

Lease Owner Cities Service Oil and Gas Corporation
Lease Name Hann "B" Well No. 1
Office Address 800 Sutton Pl. Bldg. 209 E. William, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed March 6, 1983
Application for plugging filed May 25, 1983 - verbal
Plugging commenced June 8, 1983
Plugging completed June 16, 1983
Reason for abandonment of well or producing formation Uneconomical for further production
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes - verbal

Name of Conservation Agent who supervised plugging of this well District #1
Producing formation Mississippi Depth to top 4392' bottom 4402' T.D. 4402'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	666'	-0-
				5 1/2"	4392'	2303'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 6 sacks sand and 5 sacks cement at total depth. Dug out casing head on 8 5/8" casing. Pumped 30 sacks get down surface pipe and 5 1/2" casing. Pulled 71 joints (2303') of 5 1/2" casing. Pumped down 8 5/8" casing - 3 sacks hulls, 15 sacks gel, 70 sacks common cement, 15 sacks gel, 1 sack hulls and 150 sacks cement. Plug and abandonment completed June 17, 1983.

STATE CORPORATION COMMISSION

JUN 28 1983

6-28-83

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles N. Richmond (employee of owner) or (owner-or-operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) CRichmond
800 Sutton Pl. Bldg. 209 E. William
(Address) Wichita, KS



SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1983
Jacqueline Pierce
Jacqueline Pierce Notary Public.
My Commission expires: 2-27-85