

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-21200-0000

LEASE NAME Hann

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

4950 Ft. from S Section Line

2210 Ft. from E Section Line

SEC. 26 TWP. 22s RGE. 22w (E) or (W)

COUNTY Hodgeman, Kansas

LEASE OPERATOR Buried Hills Production Co. Inc.

ADDRESS 1050 17th Street Suite 1550 Denver, Colo.

PHONE# (303) 595-0125 OPERATORS LICENSE NO. 31961

Date Well Completed 7-12-88

Character of Well Oil

Plugging Commenced 5-6-99

~~Oil~~, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-6-99

The plugging proposal was approved on 5-3-99 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Mississippi Depth to Top 4392' Bottom 4396' T.D. 4396'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface pipe	0	1303'	85/8"	1303'	None
	Production casing	0	4394'	5 1/2"	4394'	2300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mix 35 sks. of 60-40-Poz with 6% gel and 200# of hulls. Displace to bottom. Close in at 1000#. Release. Shoot pipe off at 2300'. Pull pipe to 1350'. Mix 50 sks. of 60-40-poz. 6% gel. Pull pipe to 650'. mix 90 sks. of cement and 200# of hulls. Had cement in pit. Pull pipe out. Fill 85/8' with cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Swift Services Inc. License No. _____

Address Ness City, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Buried Hills Production Co. Inc.

STATE OF KANSAS COUNTY OF Ellis, ss.

Dean Jues (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



RECEIVED STATE CORPORATION COMMISSION (Signature) Dean Jues

6-7-99 (Address) 1209 HANEY HAYS, KS.

JUN 07 1999

SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 99

CONSERVATION DIVISION
Wichita, Kansas

Charlotte Weber
Notary Public

My Commission Expires: 12-28-99