


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 4 Twp. 22S Rge. (E)16 (W)
Location as "NE/CNW&SW" or footage from lines. SW NE NE
Lease Owner Gulf Oil Corporation
Lease Name O. M. Hanshew Well No. 3
Office Address Box 661 Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole.
Date well completed 12-2 19 53
Application for plugging filed 12-3 19 53
Application for plugging approved 12-3 19 53
Plugging commenced 12-3 19 53
Plugging completed 12-3 19 53
Reason for abandonment of well or producing formation Dry Hole.

If a producing well is abandoned, date of last production --- 19 ---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 394.81 Bottom 4050.1 Total Depth of Well 4050 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	985'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole from TD to 300' with 43 Visc mud. Set bridge at 300' and spotted 20 sacks cement thru drill pipe at 300'. Filled with mud to 40' of surface, set bridge at 40' and spotted 10 sacks cement on bridge. Plugged and abandoned.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Barbour Drilling Company
Address 717 First National Bank Building Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.
W. H. Duley (employee of owner) or ~~owner/proprietor~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley
Box 544 Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 53

My commission expires April 14, 1956
W. M. Connell Notary Public.



12-9-53

WELL NO. **3** LEASE **O. M. Hahshew** COMPANY **Gulf Oil Corporation** A.F.E. **3271**
 DATE—DRILLING BEGAN **11-17-53** WELL COMPLETED **12-3-53** FIRST PRODUCTION
 SAND RECORD **Dry Hole - Plugged and Abandoned** TOTAL DEPTH **4050**
 INITIAL PRODUCTION

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
8-5/8"	32	*	*	Sals	985'				985'
#30 jts. - 8V thd. Cl. B 2 jts. - 8V thd. Cl. C-1 2 jts. - 8R thd Cl. C-1									

S- **4** T- **22S** R- **16W**

CENTER			
SW	NE	SE	NE
PAWNEE CO.,			
KANSAS			

DISTANCE H: From top of collar to KB is 0'.

DE 1993'

ELEVATION—

FORMATION RECORD:	FROM	TO
cellar	0'	4
sand		110
blue sh		425
sd		530
sh, shells		520
sd		570
sh, red bed		630
red bed, shells		765
red bed		981
anhydrite		1030
sh, shells		1735
sh, lime		1900
lime		2275
lime, sh		2345
sh, shells		2650
sh, lime		2835
lime, sh		3030
lime		3125
lime, sh		3200
lime		3377
lime, sh		3500
lime		3595
KO lime		3665
lime		3790
lime, chert		3825
lime		3869
Conglomerate		3919
Conglomerate & lime		3955
Arbuckle lime		4001
lime		4050 TD

EGW:DBG
12-16-53

PLUGGING
 PER SEC **4 T 22 R 16W**
 BOOK **140** LINE **37**