

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pawnee County, Sec. 4 Twp. 22 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE
Lease Owner Vernon Paulconer
Lease Name W. O. M. Hanshaw Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-8-66 _____ 19____
Plugging completed 10-14-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3851 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	988'	None
				7"	3848'	3031'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3851', sanded hole to 3837' and dumped 6 sacks of cement with dump bailer. Pulled 7" casing, set 10' rock bridge @ 580', mudded hole to 300' and dumped 6 yards of ready-mix cement to cap well.

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1966

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

11-2-66

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or ~~(partner or proprietor)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1966

Milton J. Volin
Notary Public.

My commission expires May 20, 1968


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company. GULF OIL CORP.
Farm. O. M. Hanshaw No. 2

SEC. 4 T. 22 R. 16W
NE SE NE
1620' fr NL NE¹/₄
565' fr EL
County Pawnee KANSAS

Total Depth. 3851
Comm. 10-17-53 Comp. 11-7-53
Shot or Treated.
Contract.
Issued. 3-20-54



CASING:
10 3/4" 988' com. w/700 sx
7" 3848' com. w/100 sx

Elevation. 1993' DF

Production. 146 BO & 50% wtr

Figures Indicate Bottom of Formations.

surface	40
sand	135
shalo	430
sand	520
rod bed	978
anhydrite	1004
rod bed	1130
shalo	1560
shalo & sholls	1850
brkn limo	1975
limo & shalo	2110
brkn limo	2290
limo	2515
shalo & limo	2710
limo & shalo	2815
brkn limo	2890
lim & shale	3080
limo	3395
limo & shalo	3495
limo	3849
Total Depth	

TOPS:

Hoobner	3389
Toronto	3410
Brown Limo	3496
Lansing	3504
Conglomerate	3814
Simpson	3821
Arbucklo	3847

Distance H: From top Collar to KB is 7'.

Initial Prod.
oil 146 Bbls. based on 8-hr. state phy.
wtr 146 bbls. potential test of 48.65
oil & 48.64 wtr.

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1966
CONSERVATION DIVISION
WICHITA, KANSAS