


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

PAWNEE County. Sec. 4 Twp. 22 Rge. 16 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines 1010' W line & 2806' S line  
Lease Owner A.F. BRANN  
Lease Name BUSTER STATE Well No.  
Office Address WICHITA, KSNASA  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 6-26-58 19  
Plugging completed 6-30-58 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT  
Producing formation Depth to top Bottom Total Depth of Well 3890 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	980'	none
				5-1/2"	3889 1/2'	3076'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3850' and found it open.  
Filled w/sand to 3830' and ran 5 sacks of cement. Pulled 5 1/2" casing, cleared hole and checked fluid to 430'. Set a 10' rock bridge from 430' to 420' and ran 5 sacks of cement. Mudded the hole to 250' and ran 15 sacks of cement. Mudded the hole to 40', set a 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor WEST SUPPLY CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. 7-26-58

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Paul Knight*  
*West Supply Co*  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of JULY, 19 58

My commission expires 9-27-58

*Thomas V. Duggin*  
Notary Public

PLUGGING  
FILE SEC 4 T22 R16W  
BOOK PAGE 105 LINE 37

JUL 26 1958  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: A. F. BRANN  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: BUSTER-STATE #1  
 LOCATION: 1010' From West Line &  
 2806-1/3' From South Line  
 Sec. 4-22-16, Pawnee County, Kans.  
 COMMENCED: September 28, 1956  
 COMPLETED: October 11, 1956.

0	158	Surface soil & sand
158	406	Shell
406	530	Sand
530	561	Shale & red bed
561	885	Shale, shells & red bed
885	975	Shale & shells
975	981	Anhydrite
981	1645	Shale & shells
1645	1915	Shale
1915	2422	Lime & shale
2558	2675	Shale
2675	3304	Shale & lime
3304	3380	Lime
3380	3504	Lime & shale
3504	3524	Lime
3524	3580	Lime & shale
3580	3890	Lime
	3890	Rotary Total Depth

Set 8-5/8" surface at 980' w/500 sacks Posmix, 2% calcium chloride.

Set 5-1/2" pipe at 3890' w/150 sx Posmix.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the BUSTER-STATE #1, 1010' from the west line and 2806-3/4' from the south line, of Section 4-22-16, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 15th day of October, 1956.

Leah Jaye Hecke  
 Notary Public

My commission expires June 16, 1959.

PLUGGING  
 FILE SEC 4 T22 R16W  
 BOOK PAGE 105 LINE 37