

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15,145,21,044-0000

LEASE NAME Otte

WELL NUMBER #1

3960 Ft. from S Section Line

4,620 Ft. from E Section Line

SEC. 4 TWP. 22 RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 3-1-88

Plugging Completed 3-23-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR MIGWIS

ADDRESS R.R. #4, Box 173AA, Great Bend, Ks. 67530

PHONE# (316-792-3636) OPERATORS LICENSE NO. 04597

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4040'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	976'	None
				5-1/2"	3935'	2,174.68'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3875' and 5 sacks cement, Shot casing at 3060', 2500' and 2150'. Pulled 54 joints of 5-1/2" casing. Allied squeezed well with 3 sacks hulls and 125 sacks ATL cement blended with 2 sacks hulls. Maximum pressure was 800 psi and shut in on vacuum.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 88

My Commission Expires:

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 7-26-91

RECEIVED
 STATE CORPORATION COMMISSION
 Iona M. Leatherman
 Notary Public
3-24-88