

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-145-21,088-0000

LEASE NAME Otte

WELL NUMBER "A" #1

3910 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 4 TWP. 22 RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-12-88

Plugging Completed 3-23-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR MIGWIS

ADDRESS R.R. #4, Box 173AA, Great Bend, Ks. 67530

PHONE# 316-792-3636 OPERATORS LICENSE NO. 04597

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3846'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	979'	None
				5-1/2"	3844'	2,591.48'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3525' and 5 sacks cement. Shot casing at 2550'. Pulled 62 joints of 5-1/2" casing. Allied squeezed well with 3 sacks hulls and 125 sacks ATL cemer blended with 2 sacks hulls. Maximum pressure was 600 psi and shutin 500 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License RECEIVED

Address Box 698, Great Bend, Kansas 67530 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss. MAR 24 1988 3-24-88

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have <sup>CONFIDENTIAL DIVISION</sup> knowledge of the facts, statements, and matters herein contained and the log of the above-described well, <sup>Wichita, Kansas</sup> filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1988

Iona M. Leatherman  
 Notary Public

My Commission Expires:

STATE NOTARY PUBLIC  
 IONA M. LEATHERMAN  
 Barton County, Kansas  
 My Appt. Exp. 9-26-91