


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-145-01093-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pawnee County. Sec. 4 Twp. 22 Rge. 16 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines 1968'S, 330'W SW/4  
Lease Owner Apex Supply, Inc.  
Lease Name Dodge Matney Well No. 3  
Office Address KK Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 12-30-61 19  
Plugging completed 1-2-62 19  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill LacKamp  
Producing formation Depth to top Bottom Total Depth of Well 3852 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	982'	None
				5-1/2"	3891'	2833'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 1 1962  
CONSERVATION  
Wichita, Kansas

Checked hole to 3858', sanded to 3825' and dumped 5 sacks of cement @ 3825' with dump bailer. Pulled 5 1/2" casing. Bailed 8-5/8" down to 980', set 10' rock bridge to 970' mudded to 300', set 10' rock bridge to 290' and ran ready mix cement to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 1962

My commission expires May 20, 1964  
Notary Public.



CONTRACTOR'S WELL LOG

COMPANY:	A. F. Brann
CONTRACTOR:	Musgrove Petroleum Corp.
FARM:	DODGE MATNEY #3
LOCATION:	1968' North of South Line 330' East of West Line Sec. 4-22-16, Pawnee County, Ks.
COMMENCED:	October 12, 1956
COMPLETED:	October 22, 1956

0	95	Surface soil & sand
95	150	Sand & clay
150	225	Shale & clay
225	440	Shale
440	531	Sand
531	705	Shale & red bed
705	970	Red bed
970	981	Red bed & anhydrite
981	1010	Anhydrite
1010	1280	Shale
1280	1800	Shells & shale
1800	2000	Shale
2000	2180	Lime
2180	2420	Lime & shale
2420	2646	Shale
2646	3175	Shale & lime streaks
3175	3380	Lime
3380	3580	Shale & lime
3580	3892	Lime
	3892	Rotary Total Depth

**RECEIVED**  
STATE CORPORATION COMMISSION  
SEP 13 1962  
CONSERVATION DIVISION  
Wichita, Kansas

Set 8-5/8" surface pipe at 982' with 500 sacks Posmix, 1% calcium chloride.  
Set 5-1/2" string at 3891' with 150 sx Posmix.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the DODGE MATNEY #3, 1968' north of the south line, and 330' east of the west line of Section 4-22-16, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling  
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 26th day of October, 1956.

Dean J. Hefke  
Notary Public

My commission expires June 16, 1959.