

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-063-20512-0000  
 API NUMBER 6-4-81

LEASE NAME Glinke

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

SE SE SE  
 Ft. from S Section Line

Ft. from E Section Line

SEC. 2 TWP. 14 RGE. 29 (E) of (W)

COUNTY Gove

Date Well Completed 5-24-81

Plugging Commenced 4-17-89

Plugging Completed 4-17-89

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by District 4 - Mr. Bosie (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
	Surface	0	377	8 5/8		None
	Casing	0	1400	5 1/2		None

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 25 1989

CONSERVATION DIVISION  
 WICHITA, KANSAS  
 04-25-89

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each case.  
~~Ran tubing to 3500'. Spot 50 sacks 65/35 10% gel 2% CC 200# hulls. Pull tubing up to 2000'. Spot 50 sacks 65/35 10% gel 2% CC 200# hulls. Pull tubing up to 1000'. Mix cement until circular. Pull tubing. Hook up to casing squeeze in 5 sacks 500# and shut in. Pressure up surface casing 1/2 bbl. 750# used 260 sacks.~~  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364

Address Box 723 Hays, Kansas 67601 BJ cementers

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

ROSEMARY SMITH  
 NOTARY PUBLIC  
 STATE OF KANSAS  
 MY APPT. EXP. MAY 1, 1991

(Signature) Ted Crawford  
 (Address) Box 723 Hays, Mo. 67601

SUBSCRIBED AND SWORN TO before me this 24 day of April, 19 89

My Commission Expires: 5/1/1991 Rosemary Smith Notary Public