

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-097-21109-0000

API NUMBER 2-26-85

LEASE NAME DAY

WELL NUMBER 1

1980 Ft. from S Section Line

2164 Ft. from E Section Line

SEC. 9 TWP. 28 SRGE. 16 or (W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced 1-7-91

Plugging Completed 1-18-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR WENERT TRISCH

ADDRESS P.O. Box 1408 Longview, Tx. 75606

PHONE# (214) 758-0646 OPERATORS LICENSE NO. 6892

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top PBTD
Rock XXX 4728 T.D. 4850

Perfs: 4731-39; 4724-21; 4695-93; 4692-91; 4664-63; 4662'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	464	8 5/8	464'	0
		0	4849	4 1/2	4849	2521--60 jts.
				3/4 rods		183
				2 3/8 thg		139

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1-8-91: Dumped 130 gallons of sand, sand at 4510. Dumped 4 sx. cement on top.

1-9-91: Shot off casing at 2521, pulled out, rigged down, moved off.

1-18-91: Halliburton top hole plugged with: 300# hulls, 10 gal, 50 cement, 10 gal,

100# hulls, 8 5/8 plug, 150 sx cement, 60 40 poz, 6 gal, 1-28-91. Dumped 1 3/4 yards

of redmix to top. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WENERT TRISCH STATE 2-1-91

STATE OF KANSAS COUNTY OF PRATT, ss. FEB 1 1991

JUDY BERRY


PLUGGING CONTRACTOR

(Employee of ~~XXXXXX~~) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Pratt Well Service, Inc.



SUBSCRIBED AND SWORN TO before me this 31st day of January, 1991

My Commission Expires: February 6, 1993

Notary Public

Glv
GREAT GUNS

Digital Log

Neutron/Density
Porosity Log

TIGHT HOLE!	FILING NO.	COMPANY <u>WENERT TRICH + KEN FLETCHER</u>
	WELL	<u>#1 DAY APT 15-097-21,109</u>
	FIELD	
	COUNTY	<u>KIOWA</u> STATE <u>KANSAS</u>
	LOCATION: <u>1980' FNL + 2164' FEL</u>	OTHER SERVICES <u>DILG</u>
	SEC. <u>9</u> TWP. <u>28S</u> RGE. <u>16W</u>	
	Permanent Datum <u>GROUND LEVEL</u> Elev. <u>2135</u>	Elev.: K.B. <u>2144</u>
	Log Measured From <u>KB</u> <u>9</u> Ft. Above Perm. Datum	D.F. _____
	Drilling Measured From <u>KELLY BUSHING</u>	G.L. <u>2135</u>

Date	<u>2-26-85</u>	FIELD PRINT
Run No.	<u>ONE</u>	
Type Log	<u>BCN-BCD</u>	
Depth—Driller	<u>4850</u>	
Depth—Logger	<u>4840</u>	
Bottom Logged Interval	<u>4820</u>	
Top Logged Interval	<u>3800</u>	
Type Fluid In Hole	<u>CHEMICAL</u>	
Salinity, PPM CL.	<u>14000</u>	
Density	<u>9.1</u>	
Level	<u>FULL</u>	
Rec. Temp., Deg F.	<u>123°</u>	
Logging Rig Time	<u>2 HOURS</u>	
Logged By	<u>GIEBLER-VOGEL</u>	
Checked By	<u>KEN FLETCHER-TERRY McLEOD</u>	

No.	Bore-Hole Record			Casing Record			
	Bit	From	To	Size	Wgt	From	To
<u>ONE</u>	<u>1 1/4</u>	<u>0</u>	<u>464</u>	<u>8 5/8</u>	<u>CONCRETE</u>	<u>0</u>	<u>464</u>
<u>ONE</u>	<u>7/8</u>	<u>464</u>	<u>4850</u>				

JAN 7 1991
CONSERVATION DIVISION
Wichita, Kansas