


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-097-10184-0000

## WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kiowa County. Sec. 9 Twp. 28S Rge. 16W (#)      (W)       
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Sunray Mid-Continent Oil Company  
Lease Name Francis Thorpe Well No. 1  
Office Address Box 1878 - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 20 19 59  
Application for plugging filed October 21 19 59  
Application for plugging approved October 22, 19 59  
Plugging commenced October 22 19 59  
Plugging completed October 31 19 59  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production      19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well       
Producing formation None Depth to top      Bottom      Total Depth of Well 4825 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Cherokee	Water	4686	4700	8-5/8"	432'	0
Mississippi	Water	4700	4715			
Viola	Water	4786	TD			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Filled hoe w/ drilling mud and kept hole full until settling stopped.  
Ten sack cement plug placed at the surface. Steel plate welded over surface pipe.

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 3 1959

CONSERVATION DIVISION  
Wichita, Kansas

11-3-59

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Stickle Drilling Company & (Halliburton)  
Address Tulsa, Okla.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Nash A. Gough (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Nash A. Gough  
Box 1878 - Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 2 day of November, 19 59

My commission expires July 13, 1963

W. E. Montgomery Notary Public.



Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

15-697-10184-0000  
Tulsa, Oklahoma  
October 23, 1959

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: October 8, 1959  
Drilling Completed: October 21, 1959

Francis A. Thorpe #1 SE  
SE SW Sec. 9-28S-16W,  
Kiowa County, Kansas.

DRILLERS LOG

Total Depth Figures Indicate Base of Formation:

Surface	0
Shale & Sand	125
Sand & Shale	280
Red Bed & Shale	655
Shale & Shells	952
Shale	1530
Shale & Shells	2150
Shale & Lime	2550
Lime & Shale	2885
Shale & Lime	4150
Lime & Shale	4280
Lime	4369
Lime & Shale	4445
Lime	4475
Shale & Lime	4570
Lime & Shale	4660
Sandy Lime & Shale	4700
Lime & Chert	4825 TD

RECEIVED  
STATE CORPORATION COMMISSION

NOV 3 1959

CONSERVATION DIVISION  
Wichita, Kansas

I, Fred E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Francis A. Thorpe #1 S/W Section 9-28S-16W, Kiowa County, Kansas.

Fred E. Stickle  
Fred E. Stickle

Lillian T. Bonham  
Notary Public

February 13, 1960  
My Commission Expires