


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 14 Twp. 22 Rge. 14 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE SE SE $\frac{1}{4}$
Lease Owner M. B. Armer
Lease Name McBride Well No. 2
Office Address 710 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed July 1 19 51
Application for plugging filed July 1 19 51
Application for plugging approved July 1 19 51
Plugging commenced July 1 19 51
Plugging completed July 1 19 51
Reason for abandonment of well or producing formation dry
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 3814 Bottom 3830 Total Depth of Well 3830 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	355	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 252 ft, pushed Halliburton plug to 250 ft., mixed 15 sacks cement & poured in on plug. Filled hole to 40 ft. with heavy mud, pushed down Halliburton plug and 1/2 sack hulls to 40 ft., mixed and poured 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to M. B. Armer
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF Spring, COUNTY OF Adair, ss.
L. C. Sproull (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) L. C. Sproull
710 Petroleum Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July, 19 51

My commission expires Sept. 17, 1951.

Rebecca Tanton
STATE CORP. Notary Public.

PLUGGING
FILE SEC 14T 22R 14W
BOOK PAGE 92 LINE 8

JUL 14 1951
7-14-51
Wichita, Ks

100

Company: M. B. Armer
 Contractor: M. B. Armer
 Drilling commenced: June 20, 1951
 Drilling completed: July 1, 1951
 Elevation: 1929 gr. 1931 D. F. 1934 R. B.

Farm: McBride - well #2
 Location: NE SE Sec 14-22-14W,
 Stafford County, Kansas
 Casing record: 8-5/8" at 395'
 cemented w/300 sacks

(figures below indicate bottoms)

Sand & shale	325
Shale & red bed	355
Shale, shells and sand strks.	780
Anhydrite	810
Red bed, shale & shells	1275
Shale & shells, salt	1720
Shale & lime	2610
Shale & lime strks.	2819
Shale & lime	3500
Lime	3602
Lime & shale	3641
Lime	3702
Shale & lime	3805
Shale	3814
Dolomite	3830
Rotary Total Depth	3830 D & A

FORMATION TOPS:

Anhydrite	780
Keokuk	3311
Brown Lime	3440
Lans.Kansas City	3453
Conglomerate	3744
Simpson	3778
Arbuckle	3814

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

By J. W. Speed

STATE OF KANSAS)
) SS
 COUNTY OF BEDFORD

Subscribed and sworn to before me, a notary public, in and for said County and State this 6th day of July, 1951.

Larry Walton
 Notary Public

My commission expires Sept. 17, 1951

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 14 1951
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 14 T 22 R 14W
 BOOK PAGE 74 LINE 8