

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 14 Twp. 22 Rge. 11W (K) (W)

Location as "NE/CNW%SW%" or footage from lines SE NE SE  
Lease Owner Herman Geo Kaiser, Oil Producer  
Lease Name McBride Well No. 1  
Office Address 909 Palace Bldg., Tulsa 3, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 12, 19 31 51  
Application for plugging filed March 20, 19 61  
Application for plugging approved March 20, 19 61  
Plugging commenced 19  
Plugging completed March 21, 19 61  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation Depth to top Bottom Total Depth of Well 3784' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8"-300' circ- 5 1/2"-3781'  
Sanded bottom of hole back to 3770' w/5 sacks cement plug thru bailer.  
Pulled 3000' 5 1/2" pipe filled hole w/mud to base of cellar and squeezed w/75 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

APR 30 1963

4-30-63  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & D Casing Pulling Company  
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
I (owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]  
909 Palace Bldg. Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 63

My commission expires 11-5-63 [Handwritten Signature] Notary Public.

Company: H. B. Armer  
 Contractor: H. B. Armer  
 Drilling commenced: 5/31/51  
 Drilling completed: 6/12/51  
 Elevation: 1933 E. F.

Well: McBride - well #1  
 Location: SE NE SE $\frac{1}{4}$  Sec. 14-22-14W,  
 Stafford County, Kansas  
 Casing record: 2-5/8" set @ 300' cemented  
 w/175 sacks  
 5" set @ 3781' cemented w/125 sacks

(figures below indicate bottom)

Sand	125
Shells & sand	300
Sand	320
Shale & red bed	780
Amphibrite	810
Shale & red bed	1040
Shale & shells	1590
Lim. brks. & shale streaks	1660
Lim. hard & shale streaks	1930
Lim & shale	2300
Shale & lim shells	2380
Shale & shells	2565
Shale & lim streaks	2750
Shale & lim	3455
Lim	3630
Lim & shale	3707
Lim	3735
Lim & shale	3775
Shale	3779
Sandy dolomite	3781
Dolomite	3784
Rotary Total Depth	3784

FORMATION TOPS: (E. F.)

Hoover	3298
Brown Lim	3424
Law.-Kansas City	3438
Viola	3707
Simpson	3732
Arvuckle	3778

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H. B. ARMER

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 2 1951

CONSERVATION DIVISION  
 Wichita, Kansas

By

*J. W. Speer*

STATE OF KANSAS

COUNTY OF WAGONER

Subscribed and sworn to before me, a notary public, and for said county and State this 19th day of June, 1951.