

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 14 Twp. 22 Rge. 14 (xx) (W)

Location as "NE/CNW&SW%" or footage from lines SW NW NW

Lease Owner Harms-Burt Drilling Co.

Lease Name G. Smith Well No. 1

Office Address Box 184, Great Bend, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 15, 1954

Application for plugging filed July 15, 1954

Application for plugging approved July 15 (orally), 1954

Plugging commenced July 15, 1954

Plugging completed July 15, 1954

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	200	8 5/8"	200	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3810' tot. D. to 200 feet.

Set plug at 200 feet and ran 20 sacks cement to 150'.

Filled with heavy mud from 150' to 35'

Set plug at 35' and capped with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company.

Address Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

H. Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. Allan Harms (Address) Box 184, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 26 day of July, 1954

My commission expires Jan. 20, 1958

Mary E Van Belt Notary Public.
RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1954
7-27-54
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
PAR SEC 14 T22 R 14W
BOOK PAGE 49 LINE 22

DRILLER'S LOG

Company: HARMS-BURT DRILLING COMPANY

Farm: C. Smith No. 1

SW NW NW Sec. 14-22S-14W
STAFFORD COUNTY, KANSAS

Commenced: July 3, 1954

Completed: July 15, 1954

Elevation: 1939 RB

0 - 150	sand
150 - 190	sand and clay
190 - 230	shale and shells
230 - 275	shale
275 - 355	sand
355 - 670	red bed
670 - 822	red bed and shale
822 - 845	Anhydrite
845 - 1625	shale and shells
1625 - 1770	lime and shale
1770 - 1900	lime
1900 - 2015	lime and shale
2015 - 2215	lime
2215 - 2515	shale and lime
2515 - 2660	shale and shells
2660 - 2800	shale and lime
2800 - 2970	lime and shale
2970 - 3119	lime
3119 - 3235	shale and lime
3235 - 3305	lime
3305 - 3430	lime and shale
3430 - 3657	lime
3657 - 3700	lime and shale
3700 - 3720	conglomerate
3720 - 3745	lime
3745 - 3750	lime and chert
3750 - 3798	shale and sand
3798 - 3810	lime
3810	TD

Set 230 feet 8 5/8" surface pipe. Cemented with 250 sacks cement and 4 sacks calcium chloride.

Tops:	Anhydrite	822
	Lansing	3430
	Arbuckle	3798

Drill stem tests:	No. 1	3550-3565	open 40 min. no blow. Shut in 15 min. 20 ft. mud. 1040# BHP
	No. 2	3605-3590	open 1 hr. strong blow throughout test. Shut in 15 min. 600' gas 90' heavily OC mud.
	No. 3	3614-3638	open 1 hr. weak blow for 4 min. Shut in 15 min. 10' mud 30# BHP
	No. 4	3778-3810	open 1 hr. fair blow. Shut in 20 min. 600' water. BHP 1218#

Ran Schlumberger

Dry, plugged and abandoned.

PLUGGING
 FEB 22 1954
 DECK FACE 49 LINE 22

STATE CORRELATION

CONSERVATION DIVISION
 STATE OF KANSAS