

Orig - State Corp. Comm.
Copy - B. A. Conner - 357 FPB
Copy - Mary Crump - Okla. City
Copy - Well File

15-185-10936-0000

Form CP-4
Rev. 12-15-80

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 13 TWP. 22 RGE. 14 N/W
Location as in quarters or footage from lines:
990' FWL & 330' FNL of SW/4

Lease Owner Phillips Petroleum Company
Lease Name Thayer Well No. 2
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed March, 1952
Application for plugging filed January 13, 1983
Plugging commenced February 17, 1983
Plugging completed February 17, 1983
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Uneconomical
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation Tor-LKC Depth to top 3302 bottom 3588 T.D. 3777

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0'	322	8 5/8	316'	-0-
Production	Oil & Wtr	0'	3772	5 1/2"	3794.63'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. MIRU Sun Oilwell Cmtg to 5 1/2" csg. Pmpd to plug as follows: 25 sx cmt (3450-3700), 2 sx hulls (3050-3450), 10 sx gel (2050-3050), 50 sx cmt (1550-2050), 10 sx gel (550-1550), 5 1/2" Wiper plug, 65 sx cmt (0-550). Max pres 450#, ISIP 250#. (All cmt 50-50 Pozmix w/4% gel and 3% CaCl. Conn to 8 5/8" and 5 1/2" annulus and pmpd 100 sx common cmt. Max press - 900#. ISIP 500#. RDMO Sun Cmtg. To weld plate over csg. Well P&A 2-17-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing
Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Area Mgr.
Box 287, Great Bend, Ks 67530
(Address)



SUBSCRIBED AND SWORN TO before me this 18th day of February, 1983

Velma L. Mog Public.
STATE CORPORATION COMMISSION

My Commission expires: February 15, 1984

FEB 22 1983

CONSERVATION DIVISION
Wichita, Kansas

Formation Record

Lease **Taylor**

Well No. **2**

FROM	TO	Formation	REMARKS
0	160	Surface soil and sand.	
160	325	Shale and shells.	
325	605	Bedded sand shale.	
605	830	Anhydrite.	
830	1680	Shale, salt, and shells.	
1680	1950	Lime and shale.	
1950	2110	Lime.	
2110	2240	Lime and shale.	
2240	2735	Shale.	
2735	3010	Lime and shale.	
3010	3299	Lime.	Tops: Nechner 3282
3299	3480	Lime and shale.	Toronto 3392 Brown Limestone 3409 Lansing-Kansas City 3422
3480	3708	Lime.	Bato LEC 3656 Viola 3688
3708	3740	Lime and shale.	Simpson 3717
3740	3777	Lime.	Arbuckle 3770

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1983
CONSERVATION DIVISION
Wichita, Kansas

3480
1927
-1495