

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22073-0000

LEASE NAME Thayer

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 13 TWP. 12 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 4-16-98

Plugging Completed 4-17-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4-22-98

RECEIVED
KANSAS CORP. COM. DIV.

EASE OPERATOR Kansas Corporation Commission 22 A 11:54

DRESS 130 S. Market, Room 2078 Wichita, Ks. 67202

PHONE#(316) 337-6200 OPERATORS LICENSE NO.

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 386' | None |
| | | | | 5-1/2" | 3849' | 1824' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from feet to feet each sack. Plugged off bottom with sand to 3250' and 5 sacks cement. Shot pipe loose @1824', pulled up to 800', pumped 10 sks. gel and 50 sks. cement, pulled to 400', pumped 50 sks. cement, pulled rest of pipe and topped off with 20 sks. cement, 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kansas Corporation Commission

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 21st. day of April, 19 98

[Signature]
Notary Public

My Commission Expires:

