

State of Kansas



15-185-01417-0000

FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts.
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

MAY 13 1963
 5-13-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Smith "AH" Well No. # 1

Location: NE SE NW Sec. 15 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3626 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

259' of 8 5/8" surface pipe, cement circulated with 250
sacks. Fill hole with mud to 250', 1st cementing plug,
1/4 sack hulls, cement with 25 sacks. Fill hole with mud
to 40', 2nd cementing plug, 1/2 sack hulls, cement with
15 sacks to base cellar, Rat hole bridged and cemented
with 2 sacks.

Very truly yours,

Audie Fleming
 Conservation Division Agent