

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 16 1963

CONSERVATION DIVISION
 Wichita, Kansas

9-16-63

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Duke Burt of Burt Drilling Co. has this

date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: High Plains Production Co.

Complete Address: 300 Insurance Bldg., Wichita, Kansas

Lease Name: Harms Well No. # 1

Location: NE SE NE Sec. 15 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3660 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burt was instructed to plug the well as follows:

237' of 8 5/8" surface pipe, cemented with 200 sacks.

Fill hole with mud to 230', 1st cementing plug, 1/4 sack

hulls, cement with 25 sacks. Fill hole with mud to 40',

2nd cementing plug, 1/4 sack hulls, cement with 15 sacks

to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent