



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
7-8-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lynch of Spector Pipe & Supply has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Spector Pipe & Supply Inc.

Complete Address: Box 169, Russell, Kansas 67665

Lease Name: Lingenfelder Well No. 1

Location: C SW NW Sec. 16 Twp. 22 Rge. 22 (E)(W)

County: Hodgeman Total Depth 4493' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Lynch was instructed to plug the well as follows:

8 5/8" to 308' circulated w/ cement. 5 1/2" to 4475' cemented.  
Open hole 4475' to 4493' Plug bottom w/ sand & 5 sacks cement  
Top of cement 3870' Mud 3870' to 850'  
Spot 80 sacks cement 850' to 550' Mud 550' to 300'  
Spot 30 sacks cement 300' to 200' Mud 200' to 40'  
Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

*Edgar J. Eves*  
Conservation Division Agent