



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
MAY 4 - 1972
CONSERVATION DIVISION
Wichita, Kansas

5-2-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kelso of Driller Prod. has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.Operator's full Name: Drillers Production Co., Inc.Complete Address: 480 4th Nat'l Bldg., Wichita, KansasLease Name: Campbell "B" Well No. 1Location: C W/2 NE SW Sec. 9 Twp. 22 Rge. 23 (E)(W)County: Hodgeman Total Depth 4631' Oil Well ☒Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☐ Lost Hole ☐Mr. Kelso was instructed to plug the well as follows:

8 5/8" to 305' circulated w/ cement. 5 1/2" to 4619' cemented.

Open hole 4619' to 4631' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4560' Mud 4560' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 300'

Spot 30 sacks cement 300' to 200' Mud 200' to 40'

Plug, & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent