

KOELSTH NO. 1
Section 33-22-15,
Pawnee County, Kansas
Schermerhorn Oil Corporation

15-145.00 254-0000

8-5/8" O. D. Casing cemented at 966'
 Dry hole

Drilling Commenced 5-16-50
 Drilling Completed 6-4-50

FROM	TO	FORMATION	REMARKS
0'	250'	Sand	
250	320	Sandy shale	
320	350	Sand	
350	405	Red bed & sand	
420	450	Sand	
450	750	Shale & shells	
750	945	Red bed & shale	
945	954	Red bed	
954	958	Chalk	
958	965	Anhydrite	
965	990	Anhydrated lime	
990	1340	Red shale & shells	8-5/8" O. D. casing cemented with 400 sacks Atlas cement at 966'
1340	1545	Shale & shells	
1545	1555	Anhydrite	
1555	1685	Shale & shells	
1685	1755	Shale & salt	
1755	1865	Lime, shells & shale	
1865	2030	Lime & shale	
2030	2425	Lime	
2425	2455	Shale	
2455	2575	Shale & shells	
2575	2900	Lime & shale	
2900	2937	Shale & shells	
2937	2969	Lime (broken)	
2969	3030	Lime & shale	
3030	3085	Shale & lime shells	
3085	3500	Lime (broken)	
3500	3565	Shale & lime	
3565	3581	Shale & shells	
3581	3680	Lime	
3680	3705	Shale & lime	
3705	3895	Lime	
3895	3960	Cherty lime	
3960	3974	Lime	
3974	4001	Cherty lime	
4001	4020	Lime	
4020	4051	Shale & lime	
4051	4085	Lime & sand	
4085	4135	Lime	

JUN 30 1950
 STATE OF OKLAHOMA
 COUNTY OF TULSA

T. D. 4135

Dry Hole

PLUGGING
 FILE SEC-33-T-22-15-1
 PAGE-10-LINE-3

COUNTY OF TULSA
 STATE OF OKLAHOMA

SCHERMERHORN OIL CORPORATION
 By *J. M. Hamner, Geol.*

Subscribed and sworn to before me a Notary Public in and For Tulsa County, Oklahoma this 29th day of June, 1950.

Opal Gulick Notary Public

My comm. expires 10-20-53.