

15-185-60888-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 3 Twp. 23S Rge. 12W (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SW SW

Lease Owner LOWENSTINE & ASSOC.

Lease Name Allen Well No. 1

Office Address 1/2 Ben Richards - 1521 Charlston St., Matoon, Ill.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 22, 19 54

Application for plugging filed September 22, 19 54

Application for plugging approved September 22, 19 54

Plugging commenced September 22, 19 54

Plugging completed September 22, 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 218' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 210' with heavy drilling mud - 1/2 sack of hulls in ahead of bottom plug at 210'. Ran 20 sacks of cement in through drill pipe and filled hole within 35' of top using 1/2 sack of hulls and 10 sacks cement. Bottom plug 210' - Top plug at 35'

9-25-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Anschutz Drilling Co., Inc.

Address 709 Union National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. E. G. Koelling

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. G. Koelling
706 Union National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 54

Charlene Barkauer
Notary Public.

My commission expires July 28, 1958

24-7368-B 3-53-20M

PLUGGING
FILE SEC 3 T 23 R 12W
BOOK PAGE 65 LINE 42

15485-00888-0000

DRILLER'S LOG

Lowerstine & Assoc.
Allen #1
SE SE SW 3-23S-12W
Stafford County, Kansas

| <u>TO</u> | <u>FROM</u> | |
|-----------|-------------|-----------------------------|
| 0 | 135 | Sand |
| 135 | 254 | Red Rock & Shale |
| 254 | 610 | Red Bed & Shale |
| 610 | 635 | Anhydrite |
| 635 | 1500 | Shale & Shells |
| 1500 | 1615 | Ft. Riley |
| 1615 | 1810 | Lime |
| 1810 | 2415 | Lime & Shale |
| 2415 | 2620 | Shale |
| 2620 | 2750 | Shale & Shells |
| 2750 | 2875 | Shale & Lime |
| 2875 | 2960 | Lime & Shale |
| 2960 | 3225 | Lime |
| 3225 | 3273 | Shale & Lime |
| 3273 | 3330 | Lime & Shale |
| 3330 | 3548 | Lime |
| 3548 | 3599 | Lime & Shale |
| 3599 | 3622 | Cherty Conglomerate |
| 3622 | 3646 | Cherty Conglomerate & Shale |
| 3646 | 3685 | Lime, Chert & Shale |
| 3685 | 3723 | Lime |
| 3723 | 3780 | Arbuckle |

COMMENCED: 9-9-54
COMPLETED: 9-22-54

CASING RECORD:
Set 218' of 8 5/8" surface casing
with 175 sacks of cement.

D & A

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Allen #1 located SE SE SW of Section 3-23S-12W, Stafford County, Kansas

ANSCHUTZ DRILLING CO., INC.

BY: *E. G. Kocling*
E. G. Kocling

Subscribed and sworn to before me this 28th day of September, 1954.

Charlene Barber
Notary Public

My Commission Expires: July 29, 1958

PLUGGING
FILE SEC 3 T 23 R 12N
BOOK PAGE 45 LINE 42