


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgemen County. Sec. 8 Twp. 22 Rge. 22 (E) w (W)
Location as "NE/CNW/SW" or footage from lines. C. SE NW
Lease Owner Sun Oil Company
Lease Name Gustav Miller Well No. 1
Office Address 1720 S. Bellaire, Suite 300, Denver, Colorado 80222
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-6 19 61
Application for plugging filed 12-16 19 74
Application for plugging approved 12-20 19 74
Plugging commenced 1-19 19 75
Plugging completed 1-25 19 75
Reason for abandonment of well or producing formation State regulations
require plugging
If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence F. Thomas
Producing formation Mississippi Depth to top 4520 Bottom 4535 Total Depth of Well 4620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	258	8 5/8	258	0
		0	4617	5 1/2	4617	204

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 800 feet. Backed off 6 joints of 5 1/2" casing. Displaced hole with 7 yards of ready mix cement. Plugged to surface

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1975
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Charlie Crowe Drilling Company
Address P. O. Box 706, Hays, KS

STATE OF Colorado, COUNTY OF Denver, ss.
D. A. Coppedge (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. A. Coppedge

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 75

Mary Marston
Notary Public.

My commission expires Nov. 22, 1975

WELL LOG

PR-4

15-083-10235-0000

COMPANY SUNRAY MID-CONTINENT OIL COMPANY

SEC. 8 T. 22S R. 22W

FARM MILLER

NO. 1


LOC. C-SE, NW

TOTAL DEPTH 4620'

COUNTY HODGEMAN CO., KANSAS

COMM. October 20, 1961 COMP. November 5, 1961

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 258' w/150 sax.
5 1/2" @ 4617' w/100 sax.

ELEVATION:

PRODUCTION:

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Rock & clay
260	Clay & shale
500	Shale
842	Red bed
848	Anhydrite
1240	Shale w/sand streaks
1557	Shale & shells
1690	Shale
2075	Shale & shells
2310=	Shale & lime
2510	Lime & shale
2732	Lime
2790	Shale & lime
2905	Lime
3860	Lime & shale
4553	Lime
4593	Lime & chert
4598	Chert & lime
4620	Lime
4620	T. D.

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1974
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 MILLER well.

Verne A. Morris

Subscribed and sworn to before me this 15th day of November 19 61

My Commission Expires: November 12, 1962

Beamsburg
NOTARY PUBLIC