


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Mark
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

HODGEMAN County, Sec. 8 Twp. 22S Rge. 22W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner SUN OIL COMPANY
Lease Name Gus Miller Well No. 5
Office Address 1720 S. Bellaire, Denver, Colorado 80222
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 4-27 19 62
Application for plugging filed 1-15 19 75
Application for plugging approved 1-17 19 75
Plugging commenced 1-28 19 75
Plugging completed 2-15 19 75
Reason for abandonment of well or producing formation State Regulations
Require Plugging

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence F. Thomas
Producing formation Mississippi Depth to top 4536 Bottom 4558 Total Depth of Well 4620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	260	8 5/8	260	0
		0	4615	5 1/2	4615	2536

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran tool to 4550'. Dumped sand to 4525'. Dumped 4 sacks cement on sand plug. Shot pipe at 2521'. Pulled 80 joints of 5 1/2" casing. Pumped 3 sacks of cottonseed hulls, 50 sacks of cement, 10 sacks of gel, 35 sacks of cement, 10 sacks of gel in hole. Released plug and displaced with 10 sacks of cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1975
2-21-75
CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Charlie Crowe Drilling Co.
Address P. O. Box 706, Hays, Kansas 67601

STATE OF Colorado, COUNTY OF Denver, ss.
D. A. Coppedge (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. A. Coppedge

SUBSCRIBED AND SWORN TO before me this 19th day of February, 19 75

(Address) Mary Marston

My commission expires My Commission expires Nov. 22, 1974

Notary Public.

WELL LOG

PR-4

COMPANY SUNRAY MID-CONTINENT OIL COMPANY

SEC. 8 T. 22S R. 22W

FARM GUS MILLER NO. 5


LOC. C-NE, SW

TOTAL DEPTH 4620'

COUNTY HODGEMAN CO., KANSAS

COMM. April 16, 1962 COMP. April 27, 1962

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 260' w/200 sax.
5 1/2" @ 4615' w/100 sax.

ELEVATION 2306' DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1975
CONSERVATION DIVISION
Wichita, Kansas

260	Shale, postrock & sand
850	Shale
865	Blaine anhydrite
1270	Shale & sand
1470	Shale
1510	Anhydrite
2080	Shale & shells
2512	Lime & shale
2760	Lime
3192	Shale & lime
3400	Shale
3690	Shale & lime
3847	Lime & shale
3870	Shale & lime
3998	Lime & shale
4150	Lime
4400	Lime & shale
4574	Lime & shale
4620	Lime
4620	T. D.

State of KANSAS }
County of BARTON } SS

I, XVERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #5 GUS MILLER well.

Xverne A. Morris

Subscribed and sworn to before me this 15th day of May 19 62

My Commission Expires: April 14, 1963

Arthur J. Miles
NOTARY PUBLIC