

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Hodgeman County, Sec. 8 Twp. 22 Rge. 22 (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE NE

Lease Owner Specter Pipe & Supply, Inc.

Lease Name Miller Estate Well No. 5

Office Address Box 169 Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 4-3-62 19

Application for plugging filed May 26, 1973 19

Application for plugging approved May 30, 1973 19

Plugging commenced 6/13 1973

Plugging completed 6/23 1973

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves

Producing formation Mississippi Depth to top 4574' Bottom 4580' Total Depth of Well 4580 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	0
				5 1/2"	4580'	3012'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 4580' to 4560'. Run 5 sacks cement from 4560' to 4530'.

Pumped 5 sacks gel mud, 80 sacks cement, 5 sacks gel mud, 30 sacks cement, 2 sacks gel mud & 10 sacks cement in 8 5/8" pipe to plug well.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 2 1973

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn's Pipe Pulling Co.

Address Box 156 Ellinwood, Kansas 67526

STATE OF Kansas COUNTY OF Russell, ss.  
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Glenn Specter*  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26th day of June, 1973

*Ruth E. Miller*

My commission expires January 5, 1977

Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SUNRAY MID-CONTINENT OIL COMPANY  
Farm- Miller Estate No. 5

SEC. 8 T. 22 R. 22W  
C SE NE

Total Depth. 4580'  
Comm. 3-21-1962 Comp. 4-3-1962  
Shot or Treated.  
Contractor. Garvey Drilling Company  
Issued. 8-18-1962

County Hodgeman  
KANSAS



Elevation. 2249' DF.

Production. 70 BOPD, NW/MISS  
4468-82

Figures Indicate Bottom of Formations.

Surface Clay & Shale	70
Shale	255
Blue Shale	315
Shale & Red Bed	785
Anhydrite	795
Sand	1070
Shale & Shells	1425
Anhydrite	1475
Shale W/Lime Strks.	1553
Shale & Shells	2007
Shale	2165
Shale & Lime	2300
Lime	2638
Lime & Shale	2810
Shale & Lime	3130
Shale	3265
Shale & Lime	3756
Lime & Shale	3915
Lime	4475
Chert	4540
Lime	4574
Lime & Sand	4580
TOTAL DEPTH	4580

TOPS:	ELECTRIC LOG
Heebner	3785
Lansing	3844
Marmaton	4224
Fort Scott	4314
Cherokee Shale	4379
Mississippi	4466
Total Depth	4580

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1973  
CONSERVATION DIVISION  
Wichita, Kansas