


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 8 Twp. 22 Rge. 22 (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Specter Pipe & Supply, Inc.  
Lease Name Miller Estate Well No. 4  
Office Address Box 169 Russell, Kans. 67665  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 3-6-62 19  
Application for plugging filed May 26, 1973 19  
Application for plugging approved May 30, 1973 19  
Plugging commenced 6/5 1973  
Plugging completed 6/23 1973  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves  
Producing formation Mississippi Depth to top 4480 Bottom 4574 Total Depth of Well 4575 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260'	0
				5 1/2"	4574'	2524'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Set plug at 4080'. Sand & 5 sacks of cement from 4080' to 4045'.  
Pumped 5 sacks gel mud, 80 sacks cement, 5 sacks gel mud, 30 sacks cement, 2 sacks gel mud & 10 sacks cement in 8 5/8" pipe to plug well.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 2 1973

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn's Pipe Pulling Co.  
Address Box 156 Ellinwood, Kans. 67526

STATE OF Kansas COUNTY OF Russell, ss.  
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John Specter*  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of June, 1973  
*Luth E. Miller*

My commission expires January 5, 1977 Notary Public.

15.083-10231-0000


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. SUNRAY MID-CONTINENT OIL CO.  
Farm. Miller Est. No. 4

SEC. 8 T. 22 R. 22W  
C NE NE

Total Depth. 4575'  
Comm. 2-22-62 Comp. 3-6-62  
Shot or Treated.  
Contractor. Garvey Drlg. Co.  
Issued. 7-7-62

County Hodgeman  
KANSAS



Elevation. 2258' DE

Production. 144 BOPD, NW

CASING:

8 5/8" 260' cem w/200 sx.  
5 1/2" 4574' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay	40
shale	260
blue shale	560
red bed	750
shale	800
Anhydrite	815
red bed & shale	900
sand	1100
shale	1400
red bed & shale	1428
Anhydrite	1463
shale & shells	1680
shale & lime	2375
lime	2875
shale & lime	3535
lime & shale	3905
lime	4430
lime & shale	4460
cherty lime	4575
Total Depth	

TOPS: SCOUT

Blaine	799
Stone Corral	1430
Heebner	3813
Douglas	3848
Lansing	3871
Base Kansas City	4168
Marmaton	4242
Ft. Scott	4328
Cherokee Shale	4387
Mississippi	4480

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1973  
CONSERVATION DIVISION  
Wichita, Kansas