

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 13 TWP. 22S RGE. 21 E/W
Location as in quarters or footage from lines:
NW NW SW

Lease Owner Cities Service Company
Lease Name Miller "AC" Well No. 1
Office Address 209 East William, 800 Sutton Place Bldg., Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 8-1-82
Application for plugging filed 7-31-82
Plugging commenced 7-31-82
Plugging completed 8-1-82
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom _____ T.D. 4930'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	361'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud laden fluid 4930' - 900'
70 sks cement @ 900'
40 sks cement @ 330'
10 sks cement @ 40'
10 sks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.
Joe K. Branum (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STATE RECEIVED
AUG 06 1982
CONSERVATION DIVISION
Wichita, Kansas

(Signature) Joe K. Branum
P. O. Box 506, Russell, KS 67665-0506
(Address)

SUBSCRIBED AND SWORN TO this 5th day of August, 19 82

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public.

My Commission expires: February 6, 1984.



EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: Cities Service Company
209 East William, 800 Sutton Place Bldg.
Wichita, Kansas 67202

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665

LEASE: Miller "AC" WELL #1

LOCATION: NW NW SW
Section 13-22S-21W
Hodgeman County, Kansas

Total Depth: 4930'

Elevation:

Commenced: 7-14-82

Completed: 8-1-82

Casing: 8-5/8" @ 361' with 300 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Clay	156'	Lime & Shale	4552'
Sand & Shale	320'	Lime	4595'
Shale	372	Lime & Shale	4688'
Sand & Shale	1349'	Lime	4752'
Anhydrite	1380'	Lime & Shale	4810'
Shale	2756'	Lime (R.T.D.)	4930'


STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Joe K. Branum

Subscribed and sworn to before me this 5th day of August, 1982,
My Commission Expires: February 6, 1984.




Notary Public

