

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Hodgeman SEC. 13 TWP. 22S RGE. 21 XX/W  
Location as in quarters or footage from lines:  
330' FWL - 2310' FSL


Lease Owner Cities Service Company  
Lease Name Miller "AC" Well No. 1  
Office Address 209 E. William, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 8-1-82  
Application for plugging filed 7-31-82  
Plugging commenced 7-31-82  
Plugging completed 8-1-82  
Reason for abandonment of well or producing formation Dry Hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4930'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	361'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 70 sacks 50-50 Pozmix 4% gel, 3% CaCl-2 at 900 Ft. Spotted 40 sacks 50-50 Pozmix 4% gel, 3% CaCl-2 at 210-332'. Put in bridge at 40 Ft. Spotted 10 sacks 50-50 Pozmix 4% gel. 3% CaCl-2 top bridge to base of collar. Spotted 10 sacks 50-50 Pozmix 4% gel, 3% CaCl-2 in rat hole. Plug and Abandon complete 8-1-82.

STATE CORPORATION COMMISSION RECEIVED

AUG 13 1982

CONSERVATION DIVISION  
Wichita, Kansas


8-13-82

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations

STATE OF Kansas COUNTY OF Sedgwick, ss.  
W. J. Devaney (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Devaney  
800 Sutton Pl. Bldg. 209 E. William  
(Address) Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 82

Jacqueline Pierce  
Jacqueline Pierce Notary Public.

My Commission expires: 2-27-85

EMPHASIS OIL OPERATIONS  
P. O. Box 506  
Russell, Kansas 67665-0506

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1982  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

OPERATOR: Cities Service Company  
209 East William, 800 Sutton Place Bldg.  
Wichita, Kansas 67202

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas 67665

LEASE: Miller "AC" WELL #1

LOCATION: NW NW SW  
Section 13-22S-21W  
Hodgeman County, Kansas

Total Depth: 4930'

Elevation:

Commenced: 7-14-82

Completed: 8-1-82

Casing: 8-5/8" @ 361' with 300 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Clay	156'	Lime & Shale	4552'
Sand & Shale	320'	Lime	4595'
Shale	372'	Lime & Shale	4688'
Sand & Shale	1349'	Lime	4752'
Anhydrite	1380'	Lime & Shale	4810'
Shale	2756'	Lime (R.T.D.)	4930'

STATE OF KANSAS )  
) ss:  
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

*Joe K. Branum*  
\_\_\_\_\_  
Joe K. Branum RECEIVED  
STATE CORPORATION COMMISSION

AUG 12 1982  
CONSERVATION DIVISION  
Wichita, Kansas

Subscribed and sworn to before me this 5th day of August, 1982.  
My Commission Expires: February 6, 1984.



*Glenda R. Tiffin*  
\_\_\_\_\_  
Notary Public