

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 185-22,493

LEASE NAME Ivy

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #2

3630 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR L. D. Drilling, Inc.

SEC. 18 TWP. 22 RGE. 11 XXX or (W)

ADDRESS RR 1 Box 183 B, Great Bend, Kansas 67530

COUNTY Stafford

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Date Well Completed 12-17-87

Character of Well D&A

Plugging Commenced 12-17-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-18-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3664'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

50 sx @ 600

50 sx @ 345

10 sx @ 40

15 sx in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. 1-19-87

Address North Main Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss. STATE CORPORATION COMMISSION

Greg Davidson (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is true and correct that the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) Greg Davidson  
RR 1 Box 183 B, Great Bend, Ks

SUBSCRIBED AND SWORN TO before me this 15th day of January, 19 88

Bessie M. DeWerff  
Notary Public

My Commission Expires: Bessie W. DeWerff 5-20-89



DRILLER'S WELL LOG

DATE COMMENCED: December 12, 1987  
 DATE COMPLETED: December 17, 1987

L. D. DRILLING, INC.  
 IVY #2  
 NW SW NW  
 Sec. 18-22S-11W  
 Stafford County, Kansas

0 - 235' Surface Soil  
 235 - 942' Sand, clay, Red bed  
 942 - 1825' Shale w/Lime  
 1825 - 3097' Lime & Shale  
 3097 - 3250' Lime  
 3250 - 3350' Lime & Shale  
 3350 - 3595' Lime  
 3595 - 3637' Lime & Shale  
 3637 - 3664' Arbuckle  
           3664' RTD

ELEVATION: 1826 K. B.

FORMATION DATA


Heebner	3100	(-1274)
Toronto		
Douglas		
Brn Lime	3233	(-1407)
Lansing	3257	(-1431)
Base K/C	3489	(-1663)
Cong.	3510	(-1684)
Viola	3532	(-1706)
Simpson	3581	(-1755)
Arbuckle	3637	(-1811)

SURFACE PIPE: set new 8 5/8"  
 @ 335' w/235' sx 50/50 poz mix,  
 2% Gel, 3% cc.


AFFIDAVIT

STATE OF KANSAS  
 COUNTY OF BARTON           SS

Greg Davidson of lawful age, does swear and state that the facts and statement herein are true and correct to the best of his knowledge.

  
 Greg Davidson

Subscribed and sworn to before me this 15<sup>th</sup> day of January, 1988

STATE CONSERVATION COMMISSION  
 .IAN 19 1987  
 CONSERVATION DIVISION  
 Wichita Kansas  
  
 Notary Public - Bessie M. DeWerff