

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
230 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15 - 185-22,524-0000

LEASE NAME Alpers

WELL NUMBER 2

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 18 TWP. 22S RGE. 11 (R) or (W)

COUNTY Stafford

Date Well Completed: 6-15-88

Plugging Commenced 6-15-88

Plugging Completed 6-15-88

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Globe Exploration

ADDRESS P. O. Box 12, Great Bend, KS 67530

PHONE# (316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well Dry D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-13-88 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? Will be by oper. If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3710'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plug #1 set at 600' w/50 sacks cement thru drill pipe

Plug # 2 set at 320' w/40 sacks cement thru drill pipe

Plug #3 set at 40' w/10 sacks cement

15 sacks in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Company, Inc. License No. 5929

Address 620 Hubbard, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) 620 Hubbard, Great Bend, KS 67530


SUBSCRIBED AND SWORN TO before me this 17 day of June, 19 88

Dorothy M. Haque  
Notary Public

STATE CORPORATION COMMISSION

6-20-88

JUN 20 1988 Form CP-4 Revised 07-87



DRILLERS WELL LOG

DATE COMMENCED: June 10, 1988

DATE COMPLETED: June 15, 1988

Globe Exploration  
Alpers #2  
C SW SE  
Sec. 18, T22S, R11W  
Stafford County, KS

0 - 574' Top Soil, Shale, Red Bed  
 574' - 599' Anhydrite  
 599 - 2818' Shale, Sand  
 2818 - 3118' Lime  
 3118 - 3123' Shale  
 3123 - 3151' Lime, Shale  
 3151 - 3256' Shale  
 3256 - 3278' Lime, Shale  
 3278 - 3524' Lime  
 3524 - 3588' Shale, Lime, Congl.  
 3588 - 3643' Chert, Lime  
 3643 - 3663' Shale  
 3663 - 3710' Sand, Lime  
 3710' RTD


Elevation: 1830 K.B.

Surface Pipe: Set new  
8 5/8" pipe, 23# @  
308' w/170 sacks 60/40  
Pozmix, 2% gel, 3% C.C.

## A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

LEONARD WILLIAMSON of lawful age, does swear and state that the  
 facts and statements herein are true and correct to the best of his knowledge.



*Leonard Williamson*  
 Leonard Williamson

SUBSCRIBED AND SWORN to before me this 17 day of June, 1988.

*Dorothy M. Hague*  
 Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JUN 20 1988

CONSERVATION DIVISION  
Wichita, Kansas