

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

STAFFORD

County. Sec. 18 Twp. 22 Rge. 11 (E) (West)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE NE SW

Lease Owner E. H. Adair

Lease Name Darr Well No. # 1

Office Address 407 W-K-H Building

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 25, 1953

Application for plugging filed June 25, 1953

Application for plugging approved June 25, 1953

Plugging commenced June 25, 1953

Plugging completed June 25, 1953

Reason for abandonment of well or producing formation Barren

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3685 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|--------------------------------|---------|------|----|------|--------|------------|
| copy of drilling log attached. | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Lowered down drill pipe and placed wooden plug @220' cemented with 20 sacks filled hole to 40' and placed #2 plug. Cemented with 10 sacks to top of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1953
7-13-53
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor E.H. Adair Oil Company
Address 407 W-K-H Building Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Kenneth W. Johnson (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth W. Johnson
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of July, 1953

My commission expires Sept 15, 1953 Notary Public.

PLUGGING
FILE SEC 18 T 22 R 110
BOOK PAGE 110 LINE 21

DRILLING LOG

CONTRACTOR: E. H. Adair

Commenced: June 16, 1953

FARM: Darr # 1

Completed: June 24, 1953

County: Stafford

T. D. 3685'

Casing: 8 5/8 @ 224' w/175 sx.

Section 18-T.22-R.11W.

Production: Dry Hole

FIGURES INDICATE BOTTOM OF FORMATIONS

| | | |
|----------------|------|------|
| Sand | 90 | |
| Shale | 100 | |
| Shale | 124 | |
| Shale | 812 | |
| Shale | 1320 | |
| Shale & Shells | 1495 | |
| Lime & Shale | 1555 | |
| Lime & Shale | 1705 | |
| Lime & Shale | 1815 | |
| Lime | 1855 | |
| Lime | 1910 | |
| Shale & Shells | 1960 | |
| Shells & Shale | 2088 | |
| Shale & Lime | 2195 | |
| Shale & Shells | 2317 | |
| Shale & Shells | 2457 | |
| Shale & Shells | 2615 | |
| Shale & Shells | 2736 | |
| Lime & Shale | 2866 | |
| Lime & Shale | 2984 | |
| Lime & Shale | 3057 | |
| Shale & Shells | 3214 | |
| Shale & Shells | 3274 | |
| Lime | 3313 | |
| Lime | 3375 | |
| Lime | 3408 | |
| Lime | 3484 | |
| Lime | 3540 | |
| Lime | 3579 | |
| Shale | 3633 | |
| Simpson | 3667 | |
| Arbuckle | 3685 | T.D. |

| | | <u>TOPS</u> | |
|--------------|------|-------------|--|
| Heebner | 3119 | (-1289) | |
| Brown Lime | 3251 | (-1421) | |
| Kansas City | 3275 | (-1445) | |
| Marmaton | 3505 | (-1675) | |
| Conglomerate | 3567 | (-1737) | |
| Viola | 3581 | (-1751) | |
| Simpson | 3620 | (-1790) | |
| Arbuckle | 3669 | (-1839) | |

CERTIFIED CORRECT

Kenneth W. Johnson
Kenneth W. Johnson

